


- NOTES:
1. CONTRACTOR SHALL POTHOLE & DETERMINE (E) INVERT ELEVATION AT THE UPSTREAM END OF THE SEWER AT LEAST (3) WORKING DAYS PRIOR TO ANY WORK ON THIS BLOCK. PROVIDE INFORMATION TO CITY REPRESENTATIVE.
 2. VERIFY NO ACTIVE CONNECTIONS PRIOR TO ABANDONING SEWER FACILITY. NOTIFY CITY REPRESENTATIVE OF ANY DISCREPANCY.
 3. WORK IN THE INTERSECTION OF 16TH STREET AND DE HARO STREET SHALL BE COORDINATED WITH SFMTA CONTRACT 1303.



DETAIL NOTE:
REMOVE BRICKS AS NECESSARY TO ACCOMMODATE (N) SEWER CONNECTION AND FILL ANNULAR SPACE BETWEEN (E) BRICK SEWER & VCP CONNECTION WITH NON-SHIRK GROUT.

SEWER SIZED BY
Y.W. YW
APPROVED BY
B.S. BS

NO.	DATE	DESCRIPTION	BY	APP.
TABLE OF REVISIONS				


REFERENCE INFORMATION & FILE NO. OF SURVEYS
20176
50236.4
54339
87635



DESIGN & ENGINEERING
CITY & COUNTY OF SAN FRANCISCO
SAN FRANCISCO PUBLIC WORKS
30 VAN NESS AVENUE, 5TH FLOOR
SAN FRANCISCO, CA 94102 - 6028

Section Mgr:	LESLEY WONG	Date:	4/25/18
Deputy Bureau Mgr:	IQBAL DHAPA	Date:	4/27/18
Bureau Mgr:	PATRICK RIVERA	Date:	4/27/18

DESIGNED:	J.KUNG	DATE:	4/20/18
DRAWN:	S.HUEY	DATE:	4/20/18
CHECKED:	J.HELMUTH	DATE:	4/20/18



SCALE:	AS NOTED
SHEET OF SHEETS	55 OF 89

VARIOUS LOCATIONS PAVEMENT
RENOVATION NO. 37 AND SEWER REPLACEMENT
DE HARO STREET SEWER REPLACEMENT
17TH STREET TO 16TH STREET
PLAN, PROFILE AND DETAIL

CONTRACT NO.	2792J
DRAWING NO.	SW-5
FILE NO.	109,993
REV. NO.	0

