



STREET	TIME	NORTHBOUND	SOUTHBOUND	EASTBOUND	WESTBOUND
During Curb Ramp and Sidewalk Construction					
Mariposa St. east of Vermont St.	8AM - 6PM	-	-	1@11	1@11
Vermont St. at Mariposa St. US-101 Off-Ramp	At Other Times	-	-	Full Roadway	Full Roadway
Per Caltrans Encroachment Permit Requirements					
Vermont St. south of Mariposa St. & Division St.	8AM - 6PM	1@11	1@11	-	-
At Other Times	Full Roadway	Full Roadway	-	-	-
Vermont St. between 16th and Mariposa Streets	9AM - 3PM (M-F)	2@11	-	-	-
At Other Times	8AM - 6PM (S/S)	2@11	-	-	-
Division St.	8AM - 6PM	Full Roadway	-	-	-
At Other Times	-	-	-	-	-
15th, 16th, 19th and 20th Streets	8AM - 6PM	-	-	1@11	1@11
At Other Times	-	-	-	Full Roadway	Full Roadway
18th St. at Connecticut St.	9AM - 4PM (M-F)	-	-	1@12	1@12
At Other Times	8AM - 6PM (S/S)	-	-	1@12	1@12
At Other Times	-	-	-	Full Roadway	Full Roadway
Kansas, Arkansas, Connecticut, De Haro at 18th Streets (See Special Instruction)	8AM - 6PM	1@12	1@12	-	-
At Other Times	Full Roadway	Full Roadway	-	-	-
Carolina Street	8AM - 6PM	1@11	1@11	-	-
At Other Times	Full Roadway	Full Roadway	-	-	-
Connecticut at 18th St.	9AM - 4PM (M-F)	1@12	1@12	-	-
At Other Times	8AM - 6PM (S/S)	1@12	1@12	-	-
At Other Times	Full Roadway	Full Roadway	-	-	-

TRAFFIC CONTROL PLAN  
2792J VARIOUS LOCATIONS #37  
CURB RAMP WORK - CONNECTICUT ST & 19TH ST

NON-WORKING HOURS



NO EXCEPTIONS TAKEN  
MAKE CORRECTIONS NOTED  
RETRACTED  
REVISE AND RESUBMIT  
SUBMIT SPECIFIED ITEM(S)

Review is only for general conformance with the design concept of the project and general compliance with the requirements of the contract documents. Any action of the contractor shall be the responsibility of the contractor. Contractor's responsibilities include, but are not limited to, actual dimensions which shall be confirmed and correlated at the job site, preferred fabrication processes and techniques of construction, coordination of the contractor's work with that of all other trades, and the satisfactory performance of the contractor's work.

Sustainable Streets Division  
San Francisco Municipal Transportation Agency  
City and County of San Francisco

By: JKC Date: 7/18/19



CMC  
TRAFFIC CONTROL  
SPECIALISTS, INC.

3450 3RD ST #3C  
SAN FRANCISCO, CA 94124  
415-206-1700 PHONE  
415-206-1711 FAX  
INFO@CMCTRAFFIC.COM

LICENSE NO 792059  
CLASS A, 31, C21  
WBE/SBE/LBE/DBE CERTIFIED  
WWW.CMCTRAFFIC.COM

- Date: 7/10/2019 Author: KR/DD Project: 2792J  
Client: PRECISION Owner: SFPD Location: SAN FRANCISCO  
TCP: 128 Job #: 1812 Rev: 2
- Comments:
- 1) WORK HOURS: 8AM - 6PM
  - 2) CONTRACTOR TO VERIFY EXISTING STRIPING IS ACCURATE PRIOR TO START OF WORK.
  - 3) ALL TRAFFIC CONTROL SHALL CONFORM TO THE LATEST EDITION OF CA MUTCD.
  - 4) ALL TRAFFIC CONTROL DEVICES SHALL BE RETROREFLECTIVE IF SETUP DURING HOURS OF DARKNESS.
  - 5) THE CONTRACTOR SHALL BE ALLOWED TO WORK AT A MAXIMUM OF THREE INTERSECTIONS AT ANY TIME IF THERE ARE MULTIPLE CURB RAMPS TO BE CONSTRUCTED ALONG A STREET, EXCEPT AS OTHERWISE NOTED IN SPECIFICATIONS.
  - 6) NO CROSSWALK SHALL BE ALLOWED TO BE CLOSED DURING CURB RAMP WORK EXCEPT DURING DEMOLITION OF CURB RAMPS IN WHICH CONTRACTOR MAY CLOSE ONLY ONE CROSSWALK AT A TIME AND PROVIDE TWO FLAGGERS TO GUIDE PEDESTRIANS TO THE OPEN CROSSWALK.
  - 7) MAINTAIN LOCAL ACCESS TO BUSINESSES AND RESIDENTS AT ALL TIME.