


SHEET NOTES:

1. CONTRACTOR SHALL CONTACT WESLEY NG AT SFPUC (415-920-4950) TO LOWER DIVISION ST BOX SEWER WATER LEVEL PRIOR TO PLACING AN INFLATABLE PLUG OR BUILDING A TEMPORARY DAM IN THE SEWER MAIN TO PREVENT BACKWATER INTRUSION FROM THE BOX SEWER.
2. SEE CR-13 FOR CURB RAMP UPGRADE AND EXACT CB LOCATIONS AND DESIGN.

DETAIL NOTES:

1. CORE DRILL (E) CONCRETE WALL TO CREATE OPENING 4" LARGE THAN THE OD OF (N) 21" VCP.
2. CLEAN OPENING SURFACE & APPLY ACTIVATED OAKUM SOAKED IN WATER-ACTIVATED RESIN, EXPANDABLE BOOT OR WATERSTOP, INSTALL TWO NO.4 REBAR HOOPS AND FILL ANNULAR SPACE WITH NON-SHRINK GROUT.
3. SEE SPECIFICATION SECTION 01 35 45 FOR PROJECT SPECIFIC SAFETY AND HEALTH REQUIREMENTS.

ACTIVATED OAKUM EXPANDABLE BOOT (TYP 360"), OR WATERSTOP (SEE NOTE 2)



SEWER SIZED BY Y.W. YW		APPROVED BY B.S. BS		REFERENCE INFORMATION & FILE NO. OF SURVEYS		DESIGN & ENGINEERING CITY & COUNTY OF SAN FRANCISCO SAN FRANCISCO PUBLIC WORKS 30 VAN NESS AVENUE, 5TH FLOOR SAN FRANCISCO, CA 94102 - 6028		Section Mgr: Deputy Bureau Mgr: Bureau Mgr:		Date: Date: Date:		DESIGNED: DRAWN: CHECKED:		DATE: DATE: DATE:		SCALE: AS NOTED		SHEET OF SHEETS 64 OF 89		VARIOUS LOCATIONS PAVEMENT RENOVATION NO. 37 AND SEWER REPLACEMENT		VERMONT STREET SEWER REPLACEMENT ALAMEDA STREET TO DIVISION STREET PLAN, PROFILE AND DETAIL		CONTRACT NO. 2792J		DRAWING NO. SW-14		FILE NO. 110,002		REV. NO. 0	
NO.	DATE	DESCRIPTION	BY	APP.																											
TABLE OF REVISIONS																															