



TRAFFIC CONTROL PLAN  
2792J VARIOUS LOCATIONS #37  
CURB RAMP WORK - 18TH ST AT CAROLINA ST



NON-WORKING HOURS




STREET	TIME	NORTHBOUND	SOUTHBOUND	EASTBOUND	WESTBOUND
During Curb Ramp and Sidewalk Construction					
Mariposa St. east of Vermont St.	8AM - 6PM	-	-	1@11'	1@11'
Mariposa St. at Vermont St. at Mariposa St./US-101 Off-Ramp	At Other Times	-	-	Full Roadway	Full Roadway
Per Caltrans Encroachment Permit Requirements					
Vermont St. south of Mariposa St. & at 15th and Division Sts.	8AM - 6PM	1@11'	1@11'	-	-
Vermont St. between 16th and Mariposa Streets	At Other Times	Full Roadway	Full Roadway	-	-
Division St.	9AM - 3PM (M-F)	2@11'	-	-	-
15th, 18th, 19th and 20th Streets	8AM - 6PM	-	-	1@12'	Full Roadway
19th St. at Connecticut St.	At Other Times	-	-	Full Roadway	Full Roadway
Kansas, Arkansas, Connecticut, De Haro at 18th Streets (See Special Instruction)	8AM - 6PM	1@12'	1@12'	-	-
Carolina Street	At Other Times	Full Roadway	Full Roadway	-	-
Connecticut at 18th St.	8AM - 6PM (M-F)	1@11'	1@11'	-	-
	8AM - 6PM (S/S)	1@12'	1@12'	-	-
	At Other Times	Full Roadway	Full Roadway	-	-

NO EXCEPTIONS TAKEN  
MAKE CORRECTIONS NOTED  
REJECTED  
REVISE AND RESUBMIT  
SUBMIT SPECIFIED ITEMS

Review only for general compliance with the project and the requirements of the contract documents. Any actual shown is subject to the requirements of the plans, specifications, and the contractor's responsibilities, which are not limited to actual dimensions which shall be confirmed and correlated at the job site, preferred fabrication processes and techniques of construction, coordination of the contractor's work with that of all other trades and the satisfactory performance of the contractor's work.

Sustainable Streets Division  
San Francisco Municipal Transportation Agency  
City and County of San Francisco

By *KVW* Date *5/14/19*



3450 3RD ST #36  
SAN FRANCISCO, CA 94124  
415-206-1700 PHONE  
415-206-1711 FAX  
INFO@CMCTRAFFIC.COM

LICENSE NO 792059  
CLASS A, 31, C21  
WBE/SBE/LBE/DBE CERTIFIED  
WWW.CMCTRAFFIC.COM

Date: 4/20/2019 Author: KR/DD Project: 2792J  
Client: PRECISION Owner: SFPDPW Location: SAN FRANCISCO  
TCP: 125 Job #: 1812 Rev: 0

Comments:

- 1) WORK HOURS: 8AM - 6PM
- 2) CONTRACTOR TO VERIFY EXISTING STRIPING IS ACCURATE PRIOR TO START OF WORK.
- 3) ALL TRAFFIC CONTROL SHALL CONFORM TO THE LATEST EDITION OF CA MUTCD.
- 4) ALL TRAFFIC CONTROL DEVICES SHALL BE RETROREFLECTIVE IF SETUP DURING HOURS OF DARKNESS.
- 5) THE CONTRACTOR SHALL BE ALLOWED TO WORK AT A MAXIMUM OF THREE INTERSECTIONS AT ANY TIME IF THERE ARE MULTIPLE CURB RAMP TO BE CONSTRUCTED ALONG A STREET, EXCEPT AS OTHERWISE NOTED IN SPECIFICATIONS.
- 6) NO CROSSWALK SHALL BE ALLOWED TO BE CLOSED DURING CURB RAMP WORK EXCEPT DURING DEMOLITION OF CURB RAMP IN WHICH CONTRACTOR MAY CLOSE ONLY ONE CROSSWALK AT A TIME AND PROVIDE TWO FLAGGERS TO GUIDE PEDESTRIANS TO THE OPEN CROSSWALK.
- 7) MAINTAIN LOCAL ACCESS TO BUSINESSES AND RESIDENTS AT ALL TIME.